

Low Carbon Investment Park Infrastructure Contract

Client:	Fife Council
Form of Contract:	NEC3
Duration:	Apr 2015 to present
NRS Role:	Principal Contractor and Main Civil Engineering Contractor



Main Description

This project consisted of the construction of the site infrastructure for a future investment park. Works included:

- Site Clearance.
- Fencing of the site.
- Excavation of 8500 m2 of material.
- Installation of drainage system including the excavation and creation of a SUDS pond. Drainage consisted of the installation of 1,483 meters of drainage pipes and various chambers.
- Installation of 2206 meters of service ducting.
- Construction of an access road (9,600m2 of surfacing)
- Installation of 850 meters of kerbing and construction of 2750 meters of footway.
- Installation of signs and application of surface lining.
- Installation of public lighting system (30 no lighting columns)
- Landscaping of the area.

