

## Gorey Regional Water Supply Scheme

<b>Client:</b>	Wexford County Council
<b>Form of Contract:</b>	Traditional IEI Form of Contract
<b>Duration:</b>	Apr 2009 to Jul 2011
<b>NRS Role:</b>	Main Civil Engineering Contractor and PSCS



### Main Description

This project involved the Laying of 36 km of Watermain Pipelines in Gorey, Co. Wexford. Works included:

- Laying of 12.45km Ductile Iron Pipelines (600mm - 350mm)
- Laying of 23.85km HPPE Pipelines (630 mm - 180 mm)
- Construction of 10 No. PRV Chambers
- Connection to Existing Reservoir
- Connections to Existing Pipeline
- Excavation and Disposal of Contaminated Coal Tar — approximately 4522 tonnes of material were removed from site and disposed of by a licensed contractor.
- Directional Drilling of Pipelines Under Large Rivers
- Tarmac Reinstatement of All Roads on Completion
- Landscaping
- Continuous Traffic Management

